

RIS				
Prepared for:		russell 🐶		
Site:		cawberry		
Work Activity:				PART OF THE RC GROUP
Project No.:		Work scope	General site works	
Created by		Date		

		5	x 5 Ris	sk Matr	ix		
L	5	5	10	15	20	25	Risk Rating (Likelihood x Consequence)
ĸ	4	4	8	12	16	20	16-25 = High Risk: - Action required to eliminate or reduce risk
E L	3	3	6	9	12	15	9-15 = Medium Risk: - Action required to reduce or control risk
н	2	2	4	6	8	10	1-8 = Low Risk: - No action required but review where necessary
00	1	1	2	3	4	5	
D		1	2	3	4	5	
	CONSEQUENCES			ES			

Activity /	Hazard	Risk	Those affected	Initial Risk Rating =			Controls introduced in order to reduce risk		Final Risk Rating=		
Process				L	с	R		L	с	R	
WORKING ON ROOFS	Injury from the fall of materials / operative from the ladder. Falling from heights.	 Falls of persons from height Falls between joists Falling of materials and tools Scaffold collapse 	Employees, Sub- Contractors, Visitors & General Public Official	4	5	20	 Roof permits to be issued for ALL roof works. Consideration to be given to protecting persons beneath against the harm. Suitable means of access to be provided, such as roof ladders, crawling boards, scaffolding and staging. Where it is possible for employed to fall edge protection must be provided. If this is not possible then alternative controls must be implemented e.g. safety nets. harnesses etc. Where access is possible alongside fragile materials such as roof lights, covers to be provided or the fragile material to be barrier off. 	2	2	4	

Title: Generic Risk Assessment Sheet Effective Date: January 2018 Revision Number: 1 Our ref: RCL17-116v2 For Russell Cawberry Internal Use Only Author: H&S Department Page: 1 of 4



WORKING ON ROOFS

6. Edge protection is always required to be in position before any
roof work begins.
7. Joists are to be fully boarded, or other safe system to be in place
before work over open joists begins.
8. Site Management to define as safe work method prior to
commencement on site and arrange for provision of suitable
access equipment and trained personnel.
9. Site Management to check method statements to ensure the
proposed working method is safe and being complied with.
10. Working alone on roofs will not normally be permitted, and never
without specific authorisation.
11. Scaffolds are erected by trained personnel. Hoists are erected by
competent persons with current test certificate.
12. Hoists and scaffolds are inspected every 7 days.
13. Operatives are trained in the use of hand tools; gloves and
goggles are worn where appropriate.
14. LPG cylinders are used in an upright position and secured, at last
3m away from sources of ignition

Title: Generic Risk Assessment Sheet Effective Date: January 2018 Revision Number: 1 Our ref: RCL17-116v2 For Russell Cawberry Internal Use Only Author: H&S Department Page: 2 of 4





ENSURE THAT THE CORRECT PPE FOR THE TASK IS WORN AT ALL TIMES.

This risk assessment should be read in conjunction with all relevant method statements, safe systems of work and associated risk assessments as detailed on the Risk Assessment Briefing Record

All relevant H&S information will be relayed to staff through inductions, toolbox talks and Information displayed around site.

Method Statement Briefing Record

Briefing delivered by:

Position:

Date:

We (the undersigned) have read and understood the attached method statement and will comply with the specified requirements and control measures. If the work activity changes or deviates from that originally envisaged, we will seek further advice and request an amended method statement.

Title: Generic Risk Assessment Sheet Effective Date: January 2018 Revision Number: 1 Our ref: RCL17-116v2 For Russell Cawberry Internal Use Only Author: H&S Department Page: 3 of 4



Name (Print)	Signature	Date

Title: Generic Risk Assessment Sheet Effective Date: January 2018 Revision Number: 1 Our ref: RCL17-116v2 For Russell Cawberry Internal Use Only Author: H&S Department Page: 4 of 4